


Public Information Meeting August 12, 2020



U.S. Route 4/I-90 Intersection Safety Enhancements I-90 Exit 9 Westbound Ramps Town of East Greenbush; Rensselaer County PIN 1089.79

Introductions

- Kelley Kircher Project Manager
 - Nick Loucks Project Designer



<u>Agenda</u>

- Project Overview
- Context/Existing Conditions
- Project Objectives
- Alternatives
- Schedule
- Cost
- Q&A



Project Overview

- NYSDOT identified US Route 4/I-90 Westbound ramp intersection during safety screening
 - 2018 High Accident Location (HAL)
 Listed as Safety Deficient Location (SDL)
 Priority Investigation Location (PIL)
- Project placed on the Capital District Transportation Committee *Transportation Improvement Program*
- Highway Safety Improvement Program (HSIP)
 - Federal Aid Program to achieve a significant reduction in fatalities and serious injuries



PIN 1089.79 5


Context - Location Map





PIN 1089.79 6

Project Location



Source: Google Earth



Department of Transportation

PIN 1089.79

Site Photos



U.S. Route 4 Looking North at Mannix Rd.



Site Photos



U.S. Route 4 Looking South from Mannix Rd.



PIN 1089.79

8

PIN 1089.79

Site Photos



U.S. Route 4 Looking Northeast at I-90 Westbound Ramp



PIN 1089.79 10

Site Photos



I-90 Westbound On-Ramp Looking East



PIN 1089.79 11

Site Photos



I-90 Westbound Off-Ramp Looking South



Crash Analysis

Type of Intersection Crash	Rt 4/I-90 Westbound Intersection	Statewide Average
Overall (c/mev) ¹	0.57	0.18
Left Turns (c/mev) ¹	0.27	0.02


- 19 crashes from June 2016 May 2019
 - 9 crashes southbound left turns onto I-90 ramp
 - 6 of 9 southbound left turn crashes resulted in personal injury
 - No crashes involving pedestrians or bicyclists



1. c/mev = crashes per million entering vehicles

Existing Conditions

2021 Traffic Volumes – vehicles per hour





Source: Google Earth

Operating Speeds

Location	Speed Limit	85 th Percentile Speed
U.S. Route 4	45 MPH	51 MPH



Project Objectives


- Primary Objective:
 - Correct safety deficiencies using cost-effective accident reduction measures such that crash frequency, severity, and vehicular conflict points are reduced
- Secondary Objective:
 - Improve overall traffic conditions using cost-effective methods to reduce delay and continuously provide an acceptable level of service, for a design period of 20 years



PIN 1089.79 16

Alternatives

Alternative #1 (Null Alternative)





Source: Google Earth

PIN 1089.79 17

<u>Alternatives</u>

Alternative #2 (Signal)







Transportation

Alternatives

Alternative #2 (Signal)







Alternatives

Alternative #3 (Roundabout)







Alternatives

Alternative #3 (Roundabout)







PIN 1089.79 21

Alternatives


Alternative #3





Alternatives

Level of Service (LOS) Analysis – 2041 Design Year PM





Source: Google Earth

<u>Alternatives</u>

Alternative #3 - Simulation





Alternatives

Additional Benefits - Roundabouts

- Result in slower speeds through intersection(1)
- Reduced crash frequency and severity⁽¹⁾
- Lower speed vehicle-pedestrian conflict
- Reduced emissions and noise
- Aesthetically pleasing

Sources: (1) National Cooperative Highway Research Program Roundabout Guide



Work Zone Traffic Control

- Construction to be sequenced along with Phase 1 improvements: one contractor, NYSDOT inspecting
- Roundabout to be built in phases
 - Some short-term closures are expected
 - Emergency services and school districts to be notified in advance
 - Night work may be used for the roundabout
- Lane closures are expected
- Minimize impact to traveling public, bus routes



Additional Information

- Environmental
 - SEQRA Type II, NEPA Class II Categorical Exclusion (pending FHWA approval)
 - NYSDEC SPDES Permit stormwater
- Public Involvement
 - Meet with local officials, coordinate with school district, emergency services
- Right-of-way
 - > No acquisitions expected; Right of Way is Without Access
- Utilities
 - Roadway lighting will be added
 - One vault will be relocated
- Landscaping
 - Center island



PIN 1089.79 27

Project Schedule

Project Phase	Anticipated Date	
Design Approval	Fall 2020	
Final Design	Winter 2021	
Bid Date	April 2021	
Construction Begins	June 2021	
Construction Substantially Complete	December 2021	



PIN 1089.79 28

Project Cost

Project Element	Cost
Construction Cost – 2020 Dollars	\$3.42 M
Inflation	\$0.10 M
Construction Cost – 2021 Dollars	\$3.52 M
Right of Way	\$0



Thank you!

- Project Manager Kelley Kircher
 - Office (518) 457-2067
 - E-Mail Kelley.Kircher@dot.ny.gov

Questions? Comments?

