

SOLAR FIELD LAYOUT FOR

ELP GRENBUSH SOLAR

APPLICANT/OWNER:

ELP GREENBUSH SOLAR, LLC

MORNER ROAD TOWN OF NORTH GREENBUSH AND EAST GREENBUSH RENSSELAER COUNTY, NEW YORK



	SHEET INDEX:
SHEET NUMBER	SHEET TITLE
1	COVER SHEET
2	OVERALL SITE PLAN
3	EXISTING CONDITIONS
4	SUBDIVISION PLAN
5	SITE PLAN
6	SITE PLAN
7	SITE PLAN
8	EROSION & SEDIMENT CONTROL PLAN
9	SITE DETAILS
10	SITE DETAILS
11	SITE DETAILS


RECORD OF SUBMITTALS	DATE	BY
SUBMITTAL TO TOWN OF GREENBUSH PLANNING BOARD	3/14/2022	BP0

SOLAR FIELD LAYOUT FOR

ELP GREENBUSH SOLAR

APPLICANT: ELP GREENBUSH SOLAR LLC 13 MORNER ROAD

TOWNS OF NORTH GREENBUSH AND EAST GREENBUSH RENSSELAER COUNTY, NEW YORK



<u>TOWN OF NORTH GREENBUSH</u>	LAMMING	DOAND	AFFRUVAL

/ISION	DATE	BY	\
			\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ CH
			ED
			THE
			COL
			AR
			ENVIRONMENTAL DESIGN
			PARTNERSHIP, LLP.
			900 Route 146 Clifton Park, New York 12065
	1	1	200 Route 140 Chrisphy, Jahry, Jyew Tork (2003


DRAWN BY CHECK BY BPO EDP PROJECT NUMBER 12864 THE ALTERATION OF THESE DOCUMENTS IN ANY WAY, UNLESS DONE UNDER THE DIRECT SUPERVISION OF A COMPARABLE PROFESSIONAL, (I.E.) ENGINEER FOR AN ENGINEER, LANDSCAPE ARCHITECT FOR A LANDSCAPE ARCHITECT OR SUPEVYOR FOR A SURVEYOR, IS A VIOLATION OF THE NEW YORK STATE EDUCATION LAW AND/OR REGULATIONS AND IS A CLASS "A" MISDEMEANOR.			
CHECK BY EDP PROJECT NUMBER THE ALTERATION OF THESE DOCUMENTS IN ANY WAY, UNLESS DONE UNDER THE DIRECT SUPERVISION OF A COMPARABLE PROFESSIONAL, (I.E.) ENGINEER FOR AN ENGINEER, LANDSCAPE ARCHITECT FOR A LANDSCAPE ARCHITECT OR SURVEYOR FOR A SURVEYOR, IS A VIOLATION OF THE NEW YORK STATE EDUCATION LAW AND/OR			
EDP PROJECT NUMBER 12864 THE ALTERATION OF THESE DOCUMENTS IN ANY WAY, UNLESS DONE UNDER THE DIRECT SUPERVISION OF A COMPARABLE PROFESSIONAL, (I.E.) ENGINEER FOR AN ENGINEER, LANDSCAPE ARCHITECT FOR A LANDSCAPE ARCHITECT OR SURVEYOR FOR A SURVEYOR, IS A VIOLATION OF THE NEW YORK STATE EDUCATION LAW AND/OR	DRAWN BY	NLZ	SH
THE ALTERATION OF THESE DOCUMENTS IN ANY WAY, UNLESS DONE UNDER THE DIRECT SUPERVISION OF A COMPARABLE PROFESSIONAL, (I.E.) FUNINEER FOR AN ENGINEER, LANDSCAPE ARCHITECT FOR A LANDSCAPE ARCHITECT OR SURVEYOR FOR A SURVEYOR, IS A VIOLATION OF THE NEW YORK STATE EDUCATION LAW AND/OR	CHECK BY	BPO	
UNLESS DONE UNDER THE DIRECT SUPERNSION OF A COMPARABLE PROFESSIONAL, (I.E.) ENGINEER FOR AN ENGINEER, LANDSCAPE ARCHITECT FOR A LANDSCAPE ARCHITECT OR SURVEYOR FOR A SURVEYOR, IS A VIOLATION OF THE NEW YORK STATE EDUCATION LAW AND/OR	EDP PROJECT NUMBER	12864	
	UNLESS DONE UNDER THE DIRECT SUPE COMPARABLE PROFESSIONAL, (I.E.) ENGIN ENGINEER, LANDSCAPE ARCHITECT FOR ARCHITECT OR SURVEYOR FOR A SURVEYOR, OF THE NEW YORK STATE EDUCATION	RVISION OF A EER FOR AN A LANDSCAPE IS A VIOLATION LAW AND/OR	


CONSTRUCTION


COVER SHEET DRAFT: NOT FOR


1 of 11 AS NOTED


FEBRUARY 1, 2022


























1 FLOW DIFFUSER LEVEL SPREADER
10 NOT TO SCALE




GRAVEL ACCESS DRIVE SECTION WITH SWALE



3 INFILTRATION TRENCH PLAN VIEW
10 NOT TO SCALE




NON-PERVIOUS GRAVEL SECTION




6. ALL EXPOSED SURFACES SHALL BE SLOPED SUFFICIENTLY TO SHED WATER (1/4" PER FOOT STANDARD) CLASS


B BROOM FINISH ALIGN JOINTS WITH CURBING OR AT 5 FT. INTERVALS (SEE NOTE).





6 VEGETATED SWALE
10 NOT TO SCALE






WARNING SIGN DETAIL

SOLAR FIELD LAYOUT FOR


ELP GREENBUSH SOLAR

APPLICANT: ELP GREENBUSH SOLAR LLC 13 MORNER ROAD

TOWNS OF NORTH GREENBUSH AND EAST GREENBUSH RENSSELAER COUNTY, NEW YORK



TOWN OF NORTH GREENBUSH PLANNING BOARD APPROVAL



DRAFT: NOT FOR CONSTRUCTION


AS NOTED

10 of 11

SITE DETAILS


FEBRUARY 1, 2022

- THE DOWNSTREAM DAM IS AT THE SAME ELEVATION OF THE TOW OF THE UPSTREAM
- EXTEND THE STONE A MINIMUM OF 1.5 FEET BEYOND THE DITCH BANKS TO PREVENT
- PROTECT THE CHANNEL DOWNSTREAM OF THE LOWEST CHECK DAM FROM SCOUR AND EROSION WITH STONE OR LONER AS APPROPRIATE
- ENSURE THAT CHANNEL APPURTENANCES SUCH AS CULVERT ENTRANCES BELOW CHECK DAMS ARE NOT SUBJECT TO DAMAGE OR BLOCKAGE FROM DISPLACED STONE. MAXIMUM DRAINAGE AREA 2 ACRES.
- CHECK DAM



- STONE SIZE USE 2" CRUSHED STONE, OR RECLAIMED OR RECYCLED CONCRETE EQUIVALENT.
- LENGTH AS EFFECTIVE BUT NOT LESS THAN 50 FEET. THICKNESS - NOT LESS THAN SIX(6) INCHES.
- WIDTH TWELVE (12) FOOT MINIMUM, BUT NOT LESS THAN THE FULL WIDTH AT POINTS WHERE INGRESS OR EGRESS OCCURS. TWENTY-FOUR (24) FOOT IF SINGLE ENTRANCE TO SITE.
- FILTER CLOTH WILL BE PLACED OVER ENTIRE AREA PRIOR TO PLACING OF STONE. SURFACE WATER - ALL SURFACE WATER FLOWING OR DIVERTED TOWARD CONSTRUCTION ENTRANCES SHALL BE PIPED ACROSS THE ENTRANCE. IF PIPING IS IMPRACTICAL, A MOUNTABLE BERM WITH 5:1 SLOPES WILL BE
- NECESSARY, WHEELS SHALL BE CLEANED TO REMOVE SEDIMENT PRIOR TO ENTRANCE ONTO PUBLIC RIGHT-OF-WAY. WHEN WASHING IS REQUIRED, IT SHALL BE DONE ON AN AREA STABILIZED WITH CRUSHED STONE WHICH DRAINS INTO AN APPROVED SEDIMENT TRAP OR SEDIMENT BASIN. ALL SEDIMENT SHALL BE PREVENTED FROM ENTERING ANY STORM DRAIN, DITCH OR WATERCOURSE THROUGH USE OF SAND
- BAGS, GRAVEL BOARDS OR OTHER APPROVED METHODS. MAINTENANCE - THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHTS-OF-WAY. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH ADDITIONAL STONE AS CONDITIONS DEMAND AND REPAIR AND/OR CLEANOUT OF ANY MEASURES USED TO TRAP SEDIMENT. ALL SEDIMENT SPILLED, DRIPPED, WASHED OR TRACKED ONTO PUBLIC RIGHTS-OF-WAY MUST BE REMOVED IMMEDIATELY. . PERIODIC INSPECTION AND NEEDED MAINTENANCE SHALL BE PROVIDED AFTER EACH RAIN.

STABILIZED CONSTRUCTION ENTRANCE




13 MORNER ROAD

- 1. CONSTRUCTION STAGING ARE TO BE 9" GRAVEL COURSE, WELL GRADED, WELL COMPACTED, TO CONFORM TO NYS DOT ITEM NO. 304.05 TYPE. MIN. COMPACTION 95% MODIFIED PROCTOR OR 9" CRUSHED STONE COURSE, WELL GRADED WELL COMPACTED, TO CONFORM TO NYS DOT ITEM NO. 304.03 TYPE 2 MIN. COMPACTION 95% MODIFIED PROCTOR
- 2. SUBGRADE MUST BE PROOF-ROLLED PRIOR TO PLACEMENT OF CRUSHED STONE.
- 3. WELL COMPACTED SUBGRADE MIN. COMPACTION 90% MODIFIED PROCTOR
- 4. WOVEN CONSTRUCTION FABRIC TO BE A.O.B.E. PROPEX GEOTEXT 315ST OR EQUAL 5. TEMPORARY STAGING AREA TO BE INSTALLED WITHOUT DISTURBANCE TO EXISTING GROUND
- TEMPORARY STAGING AREA

INSTALLATION NOTES:

- 1. AREA CHOSEN FOR STOCKPILING OPERATIONS SHALL BE DRY AND STABLE.
- 2. MAXIMUM SLOPE OF STOCKPILE SHALE BE 1:3.
- 3. UPON COMPLETION OF SOIL STOCKPILING EACH PILE SHALL BE SURROUNDED WITH EITHER SEDIMENT BARRIER OR SAN AND/OR GRAVEL BAG, THEN STABILIZED WITH VEGETATION OR
- 4. SILT FENCE TO BE INSTALLED AT THE DOWN STREAM END OF THE NATURAL SHEET FLOW





SOIL STOCKPILE


SILT FENCE GENERAL NOTES:

- 1. SILT FENCE SHALL BE PLACED A MINIMUM OF 5 FT. FROM TOE OF SLOPE, 10 FT. PREFERRED, TO PROVIDE ADEQUATE AREA FOR SEDIMENT STORAGE AND FACILITATE MAINTENANCE OF SEDIMENT CONTAINMENT AREA.
- 2. POSTS MAY BE 1.25"x1.25" (MINIMUM) HARDWOOD, TYPICALLY. FOR WIRE MESH BACK USE 2"x2" NOM. HARDWOOD, OR STEEL "T" OR "U" POSTS (11b per If). SILT FENCE SHALL BE WOVEN GEOTEXTILE FABRIC(GEOTEX 2130 OR EQUAL).
- 3. SILT FENCE ASSEMBLIES MÀY HÀVE 4 FT. OR 6 FT. POST SPACING, AND MAY OR MAY NOT HAVE MESH REINFORCEMENT. SENSITIVE AREAS TO BE PROTECTED MAY NEED TO BE REINFORCED BY USING HEAVY WIRE FENCING FOR ADDED SUPPORT
- 4. THE BOTTOM EDGE OF SILT FENCE SHALL BE BURIED A MINIMUM OF 6" BELOW GROUND. THE FENCE SHALL BE INSTALLED WITH THE POSTS ON THE DOWNSTREAM SIDE OF THE FABRIC.
- 5. MAXIMUM ALLOWABLE SLOPE LENGTHS CONTRIBUTING RUNOFF TO A SILT FENCE PLACED ON A SLOPE ARE:
- <u>STEEPNESS</u> _LENGTH (ft.) 5:1 OR FLATTER
- 6. MAXIMUM DRAINAGE AREA FOR OVERLAND FLOW TO A SILT FENCE SHALL NOT EXCEED ¼ ACRE PER 100 FEET OF FENCE WITH MAXIMUM PONDING DEPTH OF 1.5 FEET BEHIND THE FENCE; AND EROSION WOULD OCCUR IN THE FORM OF SHEET EROSION; AND THERE IS NO CONCENTRATION OF WATER FLOWING TO THE BARRIER.
- 7. MEASURES SHALL BE INSPECTED EVERY SEVEN (7) CALENDAR DAYS, AFTER EACH RAINFALL OF .5" OR MORE WITHIN A 12 HOUR PERIOD, OR DAILY DURING PROLONGED RAINFALL. MEASURES SHALL BE CLEANED AND REPAIRED AS REQUIRED.

 8. SEDIMENT SHALL BE REMOVED WHEN ACCUMULATION REACHES ONE—THIRD OF THE MEASURE HEIGHT. SEDIMENT SHALL BE







MAINTENANCE AND INSPECTION PRACTICES:

EROSION AND SEDIMENT CONTROL AND STABILIZATION MEASURES,

- 1. THE FOLLOWING IS A LIST OF EROSION AND SEDIMENT CONTROLS TO BE USED ON THIS SITE
- A) STABILIZATION PRACTICES FOR THIS SITE INCLUDE: • LAND CLEARING ACTIVITIES SHALL BE DONE ONLY IN AREAS WHERE EARTHWORK WILL BE PERFORMED AND SHALL PROGRESS AS EARTHWORK IS NEEDED
- FREQUENT WATERING OF EXCAVATION AND FILL AREAS TO MINIMIZE WIND EROSION DURING
- USE OF STABILIZATION FABRIC FOR ALL SLOPES HAVING A SLOPE OF 1V:2H OR GREATER AND FILL SLOPES 1V:3H OR GREATER. PERMANENT SEEDING AND PLANTING OF ALL UNPAVED AREAS USING THE HYDROMULCHING GRASS SEEDING TECHNIQUE
- B) STRUCTURAL PRACTICES FOR THIS SITE INCLUDE:
- PERIMETER PROTECTION USING SILT FENCES INLET PROTECTION AND OUTLET PROTECTION USING SILT FENCES
- STORM SEWER, CURBS AND GUTTERS STABILIZED CONSTRUCTION EXIT POINTS
- STORMWATER DETENTION PONDS (WHICH MAY ALSO SERVE AS A TEMPORARY SEDIMENT
- 2. THE FOLLOWING INSPECTION AND MAINTENANCE PRACTICES WILL BE USED TO MAINTAIN EROSION AND SEDIMENT CONTROLS AND STABILIZATION MEASURES:
- A) ALL CONTROL MEASURES WILL BE INSPECTED AT LEAST WEEKLY. B) ALL MEASURES WILL BE MAINTAINED IN GOOD WORKING ORDER; IF REPAIRS ARE FOUND TO
- BE NECESSARY, THEY WILL BE INITIATED WITHIN 24 HOURS OF REPORT. C) BUILT UP SEDIMENT WILL BE REMOVED FROM SILT FENCES / STRAW BARRIERS WHEN IT HAS REACHED ONE-THIRD THE HEIGHT OF THE FENCE.
- D) SILT FENCES / STRAW BARRIERS WILL BE INSPECTED FOR DEPTH OF SEDIMENT, TEARS, ETC., TO SEE IF THE FABRIC IS SECURELY ATTACHED TO THE FENCE POSTS, AND TO SEE THAT THE FENCE POSTS ARE SECURELY IN THE GROUND.
- E) THE SEDIMENT BASIN, IF PRESENT, WILL BE INSPECTED FOR DEPTH OF SEDIMENT, AND BUILT UP SEDIMENT WILL BE REMOVED WHEN IT REACHES 50 PERCENT OF THE DESIGN CAPACITY. F) TEMPORARY AND PERMANENT SEEDING AND ALL OTHER STABILIZATION MEASURES WILL BE INSPECTED FOR BARE SPOTS, WASHOUTS, AND HEALTHY GROWTH.
- G) A MAINTENANCE INSPECTION REPORT WILL BE MADE AFTER EACH INSPECTION. COPIES OF THE REPORT FORMS TO BE COMPLETED BY THE INSPECTOR ARE INCLUDED IN THIS SWPPP H) THE JOB SITE SUPERINTENDENT WILL BE RESPONSIBLE FOR SELECTING AND TRAINING THE INDIVIDUALS WHO WILL BE RESPONSIBLE FOR THESE INSPECTIONS, MAINTENANCE AND REPAIR
- ACTIVITIES. AND FILLING OUT INSPECTION AND MAINTENANCE REPORT PERSONNEL SELECTED FOR THE INSPECTION AND MAINTENANCE RESPONSIBILITIES WILL RECEIVE APPROPRIATE INSTRUCTION FROM THE JOB SITE SUPERINTENDENT. THEY WILL BE TRAINED IN ALL THE INSPECTION AND MAINTENANCE PRACTICES NECESSARY FOR KEEPING THE EROSION AND SEDIMENT CONTROLS THAT ARE USED ONSITE IN GOOD WORKING ORDER. THEY WILL ALSO BE TRAINED IN THE COMPLETION OF, INITIATION OF ACTIONS REQUIRED BY, AND THE FILING OF THE INSPECTION FORMS. DOCUMENTATION OF THIS PERSONNEL TRAINING WILL BE KEPT ON SITE WITH THE SWPPP.
- J) DISTURBED AREAS AND MATERIALS STORAGE AREAS WILL BE INSPECTED FOR EVIDENCE OF OR POTENTIAL FOR POLLUTANTS ENTERING STORMWATER SYSTEMS. K) REPORT TO THE NYS DEPARTMENT OF ENVIRONMENTAL CONSERVATION WITHIN 24 HOURS ANY NONCOMPLIANCE WITH THE SWPPP THAT WILL ENDANGER PUBLIC HEALTH OR THE ENVIRONMENT. FOLLOW UP WITH A WRITTEN REPORT WITHIN 5 DAYS OF THE NONCOMPLIANCE

ADDITIONAL EROSION CONTROL AND GRADING NOTES:

- MINIMAL EROSION CONTROL DEVICES ARE ILLUSTRATED ON SITE PLAN IN A SCHEMATIC MANNER BASED ON NY STATE GUIDELINES FOR EROSION AND SEDIMENT CONTROL. IT WILL BE NECESSARY TO ADJUST THE ACTUAL LOCATION AND QUANTITY OF EROSION CONTROL DEVICES DEPENDING UPON FIELD CONDITIONS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR IMPLEMENTING THESE MEASURES AS REQUIRED TO PROTECT THE SITE.
- 2. SLOPES SHALL TYPICALLY BE GRADED AT A MAXIMUM OF 3:1 (3 HORIZ. 1 VERT.) WITHIN ALL CUT OR FILL AREAS, UNLESS OTHERWISE DESIGNATED ON PLANS.
- 3. SEED SHALL BE A COMMERCIALLY AVAILABLE MIXTURE OF PERENNIAL RYE AND UTILITY GRADE
- FESCUE. PERCENTAGE OF PERENNIAL RYE SHALL NOT EXCEED 50%. 4. SEEDED AREAS SHALL BE FULLY COVERED WITH A LEAN STRAW OR MULCH MATERIAL. IF ORDERED BY THE ENGINEER OR MUNICIPALITY, A BIODEGRADABLE NETTING (E.G., EXCELSIOR
- BLANKET, COIR GEOTEXTILE) SHALL BE ANCHORED OVER SEEDED AREAS WHICH DEMONSTRATE "RILLING" OR OTHER EROSION PROCESSES.
- TOPSOIL AND SEED SHALL BE REAPPLIED TO ANY AREAS WHICH FAIL TO ESTABLISH AS A RESULT OF INITIAL APPLICATION.
- SILT FENCE BARRIERS SHALL BE PLACED WITHIN ALL AREAS OF EXPOSED SLOPES TO CONTROL SOIL EROSION DURING AND AFTER CONSTRUCTION.
- 7. ALL STORM OUTFALLS SHALL RECEIVE RIP RAP IMMEDIATELY UPON INSTALLATION (AS PER
- EROSION CONTROL (ERO-MAT) OR APPROVED EQUAL, SHALL BE INSTALLED ON ALL 2:1 SLOPES: AN ORGANIC FIBER PROTECTIVE MAT, HALF INCH LAYER OF CHOPPED STRAW, KNITTED INTO A RUGGED MAT WITH A THIN NETTING OF PHOTODEGRADABLE POLYPROPYLENE. SECURE MAT TO SLOPE WITH 6" STEEL U-SHAPED STABLES, 2 STAPLES PER SQUARE YARD, OR AS PER MANUFACTURER'S INSTRUCTIONS.
- STREAM REACHES ON-SITE AND DOWNSTREAM OF CONSTRUCTION SHALL NOT HAVE SUBSTANTIAL VISIBLE CONTRAST RELATIVE TO COLOR, TASTE, ODOR, TURBIDITY AND SEDIMENT DEPOSITION FROM THE REACHES UPSTREAM OF THE CONSTRUCTION ACTIVITY.
- 10. VEHICULAR ACCESS POINTS SHALL BE MONITORED AND INSPECTED AT THE SAME FREQUENCY AS EROSION CONTROL FEATURES TO INSURE THAT DEPOSITS OF SAND, SILT OR OTHER MATERIAL IS NOT BEING DEPOSITED ON PUBLIC ROADWAYS. IN THE EVENT ANY SIGNIFICANT DEPOSITS OCCUR THEY SHALL BE CLEANED UP IMMEDIATELY.
- 11. KEEP ALL CONSTRUCTION EQUIPMENT, TOPSOIL STOCKPILES AND ANY TEMPORARY/PERMANENT GRAVEL AREAS OFF FUTURE SEPTIC AREAS.

SEQUENCE OF CONSTRUCTION ACTIVITIES:

₹ TRUSS RODS (ALL GATES

WITH CORNER FITTINGS)

3' NOMINAL

GATE POST (WOOD)

GROND CLEARENCE

1. CONSTRUCT TEMPORARY CONSTRUCTION EXITS AT LOCATIONS SHOWN.

— 10'TO 24'(SIZE OF GATE GIVEN PROPOSAL)-

— LEAF LENGTH —

— AUTOMATIC GATE CLOSURE

TURNBUCKLE -

GROUND LINE

VERTICAL MEMBER REQUIRED

WHEN GATE LEAF IS 8' OR GREATER

2. NSTALL PERIMETER SILT FENCES AND TEMPORARY SEDIMENT BASIN IN THE LOCATIONS SHOWN AND OTHER LOCATIONS AS NECESSARY TO STABILIZE THE SITE.

– NOTCH POST AND DOWEL WITH \S " X 5" STEEL PIN AT END OF EACH BRACE $-\!-\!$

2 APPROACH SPANS MAY BE NECESSARY (SEE END AND CORNER DETAILS)

— 4" BRACE

72" - 6"x6" WIRE MESH FENCE -

APPROAC POST (WOOD)


6" MIN DIA.

- 3. BEGIN CLEARING AND GRUBBING OPERATIONS. CLEARING AND GRUBBING SHALL BE DONE ONLY IN AREAS WHERE EARTHWORK WILL BE PERFORMED AND ONLY IN AREAS WHERE BUILDING IS
- PLANNED TO COMMENCE WITHIN 14 DAYS AFTER CLEARING AND GRUBBING.
- 4. FREQUENT WATERING OF THE EXCAVATION AND FILL AREAS SHALL BE DONE TO MINIMIZE WIND EROSION.
- 5. COMMENCE SITE GRADING AND INSTALLATION OF STORMWATER MANAGEMENT FEATURES.
- 6. DISTURBED AREAS OF THE SITE WHERE CONSTRUCTION ACTIVITY HAS CEASED FOR MORE THAN 14 DAYS SHALL BE TEMPORARILY SEEDED AND WATERED.
- 7. INSTALL PROTECTIVE SILT FENCES / BARRIERS AT THE LOCATIONS OF ALL GRATE INLETS, CURB INLETS, AND AT THE ENDS OF ALL EXPOSED STORM SEWER PIPES.
- 8. TRENCHING FOR UNDERGROUND CONDUITS
- 9. INSTALLATION OF EQUIPMENT PAD(S)
- 10. PILE INSTALLATION OF SOLAR RACKING SYSTEM AND SOLAR PANELS.
- 11. INSTALLATION OF ABOVE-GROUND WIRING.
- 12. INSTALLATION OF OVERLAND FLOW DISPERSION DEVICES.
- 13. TOPSOIL REPLACEMENT, FINAL GRADING AND SEEDING AND PLANTING.
- 14. INSTALLATION OF FENCING AND REQUIRED SIGNAGE.
- 15. REMOVAL OF SILT FENCE, STABILIZED CONSTRUCTION ENTRANCES, AND OTHER STORMWATER MANAGEMENT FEATURES ONCE SITE HAS REACHED 80% FINAL STABILIZATION.

SOIL RESTORATION:

AS PER CHAPTER 5 OF THE NEW YORK STATE STORMWATER MANAGEMENT DESIGN MANUAL, SOIL RESTORATION IS REQUIRED ON THIS SITE IN ALL NON—IMPERVIOUS AREAS ONCE FINAL SUBGRADE ELEVATION IS ACHIEVED. IN AREAS OF CUT OR FILL THE SOILS SHALL BE AERATED AND 6 INCHES OF TOPSOIL SHALL BE APPLIED. IN AREAS OF HEAVY CONSTRUCTION TRAFFIC (ESPECIALLY IN AREAS 5 TO 25 FEET FROM BUILDING, BUT NOT WITHIN 5 FEET OF FOUNDATION WALLS) THE FOLLOWING RESTORATION MUST BE APPLIED:

- 1. APPLY 3 INCHES OF COMPOST OVER SUBSOIL.
- 2. TILL COMPOST INTO SUBSOIL TO A DEPTH OF AT LEAST 12 INCHES USING A CAT-MOUNTED RIPPER, TRACTOR-MOUNTED DISC, OR TILLER, MIXING, AND CIRCULATING AIR AND COMPOST INTO SOIL. 3. ROCK-PICK UNTIL UPLIFTED STONE/ROCK MATERIALS OF 4 INCHES AND LARGER SIZE ARE CLEANED
- 4. APPLY TOPSOIL TO A DEPTH OF 6 INCHES 5. VEGETATE AS REQUIRED BY APPROVED PLAN.



LINE POST SPACING


15' MAX

U __!

LINE POST (WOOD)

3" MIN DIA





1. CONCRETE WASHOUT FACILITY SHALL BE LOCATED A MINIMUM OF FIFTY 1. FEET (50') FROM SENSITIVE AREAS. CONCRETE WASHOUT FACILITY SHALL BE CONSTRUCTED AND MAINTAINED IN SUFFICIENT QUANTITY AND SIZE TO CONTAIN ALL LIQUID AND CONCRETE WASTE ENERATED BY WASHOUT OPERATIONS.

2. THE BASIN DIMENSIONS DEPICTED ABOVE ARE REQUIRED MINIMUMS. (APPROXIMATELY 60 GALLONS OF WASTE AND WATER PER TRUCK). PLASTIC LINING MATERIAL SHALL BE A MINIMUM 10 MIN POLYETHYLENE SHEETING AND SHOULD BE FREE OF HOLES, TEARS, OR OTHER DEFECTS 5. THAT COMPROMISE THE IMPERMEABILITY OF THE MATERIAL

4. WASHOUT FACILITY MUST BE CLEANED, OR NEW FACILITES MUST BE

LATH AND FLAGGING ON THREE SIDES SAND BAG-**PLASTIC** SECTION (A-A') MAINTENANCE AND CLEANING

DO NOT DISCHARGE LIQUID OR SLURRY TO WATERWAYS, STORM DRAINS OR DIRECTLY ONTO GROUND DO NOT USE SANITARY SEWER WITHOUT LOCAL APPROVAL. PLACE A SECURE NON COLLAPSING, NON-WATER COLLECTING COVER

OVER THE FACILITY PRIOR TO PREDICTED WET WEATHER TO PREVENT ACCUMULATION AND OVERFLOW. REMOVE AND DISPOSE OF HARDEN CONCRETE AND RETURN THE STRUCTURE TO A FUNCTIONAL STATE. INSPECT THE WASHOUT FACILITY FOR SIGNS OF WEAKENING OR DAMAGE AND REPAIR AS NESSESARY(RELINE THE STRUCTURE WITH NEW POLY SHEETING AFTER EACH CLEANING).


CONSTRUCTED AND READY FOR USE ONCE THE WASHOUT IS 75% FULL CONCRETE WASHOUT FACILITY


SOLAR FIELD LAYOUT FOR

RENSSELAER COUNTY, NEW YORK


ELP GREENBUSH SOLAR APPLICANT: ELP GREENBUSH SOLAR LLC

TOWNS OF NORTH GREENBUSH AND EAST GREENBUSH





TOWN OF NORTH GREENBUSH PLANNING BOARD APPROVAL



DRAFT: NOT FOR CONSTRUCTION

AS NOTED

11 of 1

SITE DETAILS

FEBRUARY 1, 2022